

FAA CRS # OMKR399L // EASA CRS # 145.5994 13251 East Control Tower Road, Englewood, CO 80112 303.799.8906 – 303.799.0634 Fax

DATE: November 12, 2020

TO: Wes Lumry, Peregrine - Vice President of Business Development

FROM: Ernest Smith, Straight Flight, Inc.

RE: Gulfstream G150 Flap and Slat Actuator Heater System (FSAHS) STC installation for aircraft installs 3 through 5.

FIRM FIXED PRICE QUOTE

Straight Flight has been requested to perform the following: 1) Install the Peregrine FSAHS STC on 12 jackscrew actuators located in both wings – 6 actuators per wing, heater system control box under the forward fuselage fairing, cockpit controls, circuit breakers and related wiring. 2) Customer to supply STC kit with acceptable paperwork – including all STC items except standard install hardware and sealants. 3) Complete paint touch up of removed wing panels to match existing scheme. 4) Complete required systems test post STC install. 5) Complete required paperwork for return to service with amended weight and balance.

Quote Notations:

- Price based on open electrical conduit behind forward galley removal of galley for wiring access is not included in this quote.
- STC kit must include all wiring with identification stamping, connectors, relays, circuit breakers pins, and STC specific parts detailed within the Peregrine drawing bill of materials
- Estimated time for STC completion; 15 days install + 3 days paint = 18 calendar days
- All physical aircraft work to be accomplished at Centennial Airport (KAPA) within Straight Flight's facilities.
- Pricing is valid for 120 days from the date of this estimate.

##